Dated 19th February 1913.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 5th March 1913, for completing the restoration of Bolappanhalli tank, Registered No. 11, Closepet Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1914.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for completing the restoration of Bolappanhalli tank;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Southern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate estimate of quantities and also the sanctioned rates for completing the restoration of Bolappanhalli tank, Registered No. 11, of Closepet Sub-Taluk.

Items.	*Per.*	*Quantity.*	*Rate.* Rs. a. p.
BUND.			
Earthwork excavation	C. yd.	106·3	0 2 0
Do raising bund	„	7,031	0 2 6
Do to breach	„	11,254	0 3 6
Do excavation for foundation of revetment	„	558	0 2 0
New stone work	„	2,449	1 0 0
Clearing site in breach	„	2,944	0 2 0
Excavating and refilling with puddle the breach ...	„	196	0 3 6
Baling water		Lump sum	300 0 0
Cutting steps and grips at sites of breach ...		Do	50 0 0
Constructing jelly drains in breach		Do	100 0 0
Refining old grade stones	No.	·8 each	0 4 0
New grade stones	„	13 „	1 4 0
New bench mark stones	„	2 „	2 8 0
New gauge stones	„	1 „	15 0 0
Gravel backing	C. yd.	1,340	0 6 0
New tank R. No. stone	No.	1 each	5 0 0
Date stone	„	1 „	3 0 0
Index stones	„	21 „	0 4 0
Turfing	S. yd.	8,862	0 0 8
SLUICE.			
Burnt stone slabs	S. ft.	130½	0 5 0
Boring orifice for guide slabs	No.	2 each	3 0 0
Plug rod with lock, etc.		Lump sum	10 0 0
Baling water		Do	200 0 0
Plastering with surki mortar	Sqr.	9·63	3 0 0
WASTE WEIR.			
Surki chunam plastering	„	2·00	3 0 0
Earthwork	C. yd.	985	0 4 0
Brick in surki mortar	C. ft.	610	0 3 6
Burnt stone slabs	S. ft.	90	0 5 0
Cement concrete over rocking portion	C. ft.	44	0 12 0
Rough stone work	C. yd.	219	1 0 0
Benching rock	S. ft.	120	0 12 0

Items.	*Per.*	*Quantity.*	*Rate.* Rs. a. p.
WEIR CHANNEL.			
Earthwork excavation in soft rock	C. yd.	3,200	0 5 0
Blasting rock	„	424	1 8 0
Excavation, ordinary soil	„	3,156	0 2 0
Revetting with blasted stones		Lump sum	100 0 0
WIDENING THE ROAD TUNNEL.			
Earthwork	C. yd	209	0 2 0
Burnt stone in chunam	C. ft.	747	0 3 0
Burnt stone slabs, dressed	S. ft.	88	0 5 0
Pointing with chunam	Sq.	2·80	2 0 0
Dressing over parapet walls	S. ft.	115	0 2 0
Dismantling abutment and wings		Lump sum	5 0 0
Metalling over road wing	S. yd.	80	0 2 0
Earthwork filling road	C. yd.	27	0 1 6
Rough stone work, new	„	34	1 0 0
SLUICE CHANNEL.			
Earthwork excavation channel	C. yd.	2,481	0 2 0
Do foundation	„	25	0 2 0
Concrete in surki	C. ft.	435	0 3 0
Do in cement	„	25	0 12 0
Burnt stone in chunam	C. ft.	1,367	0 3 0
Pointing with chunam	Sq.	7·63	2 0 0
Burnt stone slabs, dressed	S. ft.	430	0 5 0
Rough stone work, new	C. yd.	40	1 0 0
Dismantling sluice ... ... / Relieving weirs		Lump sum	380 0 0

J. E. A. D'CRUZ,
Executive Engineer.

TUMKUR DIVISION.

FORM OF ADVERTISEMENT.

Dated 20th February 1913.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 15th March 1913, for restoring Puravara Suppadevarakere, Registered No. 229, Maddagiri Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1913.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Puravara Suppadevarakere," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Northern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.